

भारत सरकार
वाणिज्य और उद्योग मंत्रालय
सीपज़ विशेष आर्थिक क्षेत्र प्राधिकरण
अंधेरी (पूर्व), मुंबई - 400096



Government of India
Ministry of Commerce & Industry
SEEPZ Special Economic Zone Authority
Andheri (E), Mumbai - 400096

वेबसाइट: www.seepz.gov.in | ई-मेल: dcseepz-mah@nic.in | टेलीफोन: 022-28290856/28294700

File No. E-OPT-11/179/2022-EO/14016

Date: 01/12/2025

Notice for Inviting Quotations

Subject: Repairing of Drainage and Replacement of MS Gratings with Frame in front of Service Centre Building, SEEPZ-SEZ.

This is to inform that the SEEPZ-SEZ Authority invites sealed single-packet quotations for the work of Repairing of Drainage and Replacement of MS Gratings with Frame in front of Service Centre Building, SEEPZ-SEZ, as per the details mentioned below:

Scope of Work:

1. Dismantling of existing damaged drain portion and MS gratings.
2. Excavation for new drainage in required size (depth - 18 inches, width - 15 inches).
3. Providing and laying Plain Cement Concrete (PCC) bed for drain foundation.
4. Constructing drain walls with brick masonry / RCC as per standard specifications.
5. Providing cement plaster to the inner drain walls to ensure smooth flow.
6. Fabrication, supply, and installation of heavy-duty MS gratings with frame (load-bearing type) over the drain.
7. Finishing, testing, and handing over the drainage system in proper working condition.

Proposed Estimate Details:

Sr. No.	Description of Item (as per CPWD DSR 2023)	Unit	Qty.	Rate (Rs)	Amount (Rs)
1	Earthwork in excavation by mechanical means (Hydraulic excavator)/manual means in trenches for foundations, drains, etc. not exceeding 1.5 m in width, including dressing of sides and disposal of excavated earth (lead up to 50 m).	Cum	6.25		
2	Providing and laying cement concrete 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) as bed for drain.	Cum	1.50		
3	Brick work in cement mortar 1:5 (1 cement : 5 coarse sand) with F.P.S. bricks of class designation 7.5 in foundation and plinth.	Cum	5.00		
4	12 mm thick cement plaster in 1:4 (1 cement : 4 fine sand) on brick surfaces inside drain walls and top edges.	Sqm	40.00		

5	Fabrication, supply and fixing of MS gratings: Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	450.00		
6	Demolishing brick work manually/by mechanical means including stacking of serviceable material and disposal of unserviceable material.	Cum	2.00		
7	Backfilling with excavated earth (excluding rock) in layers not exceeding 20 cm, consolidating each deposited layer by ramming and watering.	Cum	2.50		
	Total Amount				

Payment Terms

- 7. Payment Terms:** Payment will be released upon submission of the bill and satisfactory completion of the work to the Authority's satisfaction.
- 8. GST Exemption:** SEEPZ-SEZ Authority is exempted from GST as per Notification No. 18/2017 – Integrated Tax (Rate) dated 05.07.2017. Hence, bidders must quote their rates **excluding GST**.
- 9. Completion Period:** The work shall be completed within **15 days** from the date of issue of the Work Order. (Extension may be granted, if required and approved.)
- 10. Submission of Quotations:** Quotations should be submitted in a **sealed single packet** on or before **04.12.2025 at 3:00 PM** at the SEEPZ-SEZ Office.
- 11. Opening of Quotations:** Quotations will be opened on the **same day**, i.e., **04.12.2025 at 4:00 PM**.
- 12. Selection Criteria:** The **lowest (L1) bidder** will be considered for award of work, subject to verification and approval by the Competent Authority


 (Aman Kumar Sharma)
 ADC/Estate
 SEEPZ SEZ Authority